DISASTER RECOVERY & BACKUP PLAN

Network Security Architecture Programme

Document Reference: SEC-DOC-007 | Version 1.0 | March 2026

CONFIDENTIAL — INTERNAL USE ONLY

RTO: 4 Hours | RPO: 1 Hour | DR Site: Active — Replication Confirmed

1. Document Information

Document Title	Disaster Recovery & Backup Plan
Document Reference	SEC-DOC-007
Version	1.0
Date	March 2026
Classification	**CONFIDENTIAL — INTERNAL USE ONLY**
Status	**APPROVED — DR replication confirmed. First failover test scheduled Q3 2026.**
RTO Target	4 hours from declaration of disaster
RPO Target	1 hour maximum data loss
Primary DC	Data Centre — 172.16.30.x (DC Firewall: 172.16.30.1)
DR Site	Disaster Recovery Site — IP addresses pending provisioning (Observation DR-08)
Replication	Confirmed — Core Banking DB (172.16.30.20) and Backup (172.16.30.40) replicate to DR site via dashed replication links
Owner	Business Continuity Manager
Related Documents	SEC-DOC-001 Security Architecture Overview v2.0 | SEC-DOC-008 Security Controls & Hardening Checklist v2.0

1.1 Purpose

This document defines the Disaster Recovery (DR) and Backup strategy for the organisation's critical banking infrastructure. It establishes the recovery objectives, describes the replication architecture, documents failover and failback procedures, and defines the testing schedule. The plan ensures the organisation can restore critical systems within defined RTO and RPO targets following any major incident that renders the primary Data Centre unavailable.

1.2 Scope

This plan covers the following systems and zones:

- Data Centre zone (172.16.30.x) — Core Banking Server, Core Banking DB, Transaction DB, Storage, Backup
- Disaster Recovery Site — Replication node, DR Database, DR Backup
- SOC zone — Wazuh SIEM backup and DR monitoring capability
- All replication links and backup jobs defined in this document

The following are out of scope for this plan: branch office recovery, ATM network recovery (covered by ATM vendor DR SLA), and workstation/endpoint recovery.

2. Recovery Objectives

2.1 RTO and RPO Targets

The following recovery time and recovery point objectives are defined per system tier. These are contractual commitments agreed with the business and reviewed annually.

System	Tier	RTO	RPO	Justification
Core Banking DB 172.16.30.20	**TIER 1 — Critical**	**2 hours**	**15 minutes**	Core banking transactions. Any data loss beyond 15 min is financially material.
Transaction DB 172.16.30.21	**TIER 1 — Critical**	**2 hours**	**15 minutes**	Payment settlement data. Regulatory requirement for near-zero RPO.
Core Banking Server	**TIER 1 — Critical**	**3 hours**	**1 hour**	Application layer — recovers after DB tier.
Payment Gateway 172.16.50.10	**TIER 1 — Critical**	**3 hours**	**1 hour**	PCI-DSS scope. Must restore within business hours.
Banking App 172.16.20.10	**TIER 2 — High**	**4 hours**	**1 hour**	Customer-facing. Target restoration within 4-hour SLA window.
Mobile Backend 172.16.20.11	**TIER 2 — High**	**4 hours**	**1 hour**	Mobile channel. Co-recovers with Banking App.
Active Directory 172.16.60.10	**TIER 2 — High**	**4 hours**	**1 hour**	Authentication dependency for all zones.
Identity Services 172.16.60.x	**TIER 2 — High**	**4 hours**	**2 hours**	DNS, RADIUS, DHCP — required before apps can function.
Wazuh SIEM 172.16.66.10	**TIER 3 — Standard**	**8 hours**	**4 hours**	SOC monitoring. Non-critical during initial recovery phase.
SOC Dashboard 172.16.66.30	**TIER 3 — Standard**	**8 hours**	**4 hours**	Analyst access — secondary to system recovery.
Branch Office Connectivity	**TIER 3 — Standard**	**24 hours**	**4 hours**	Branch staff can work offline for limited period.
DR Site Infrastructure	**TIER 0 — Pre-built**	**N/A**	**N/A**	DR site must be ready before any failover begins.

Overall RTO: 4 hours from formal disaster declaration to restoration of all Tier 1 and Tier 2 systems.

Overall RPO: 1 hour maximum data loss for all Tier 1 and Tier 2 systems. Tier 1 databases target 15-minute RPO via continuous replication.

3. Disaster Recovery Architecture

3.1 Primary Data Centre

The primary Data Centre (172.16.30.x) is the production environment hosting all Tier 1 critical systems. It implements a dual-firewall architecture:

- DC Firewall (172.16.30.1) — zone entry firewall controlling all inbound traffic from the core network
- DB Firewall — dedicated firewall protecting the database tier from the application tier
- Core Banking Server — primary banking application backend
- Core Banking DB (172.16.30.20) — primary banking database
- Transaction DB (172.16.30.21) — primary transaction database
- Storage — primary storage array with bidirectional sync to Backup
- Backup (172.16.30.40) — backup server and replication source to DR site

3.2 Disaster Recovery Site

The DR site is geographically separate from the primary Data Centre. It receives continuous replication from the primary site and is maintained in a warm standby state. The DR site contains:

- Replication node — receives and validates all incoming replication streams from primary DC
- DR Database — mirror of Core Banking DB and Transaction DB maintained within RPO target
- DR Backup — offline backup copy held at DR site independent of the replication stream

> **Pending:** DR node IP addresses are not yet assigned (Observation DR-08 from SEC-DOC-008 v2.0). IP provisioning must be completed before the Q3 2026 failover test. Network team action required by Q2 2026.

3.3 Replication Architecture

Two independent replication paths run from the primary DC to the DR site, both shown as dashed monitoring/replication lines in the confirmed architecture:

Source	Destination	Method	Frequency	Protocol	Status
Core Banking DB 172.16.30.20	DR Database	Continuous async log shipping	Near real-time (~5 min lag)	TCP 5432 / 1521	**ACTIVE**
Transaction DB 172.16.30.21	DR Database	Continuous async log shipping	Near real-time (~5 min lag)	TCP 5432 / 1521	**ACTIVE**
Backup 172.16.30.40	DR Backup	Scheduled full + incremental	Daily full Hourly incremental	TCP 9000 / 443	**ACTIVE**
Wazuh SIEM 172.16.66.10	DR Backup Storage	Nightly SIEM backup	Daily	TCP 443	**ACTIVE**
Core Banking Server	DR Site	Application image snapshot	Daily	TCP 9000	**ACTIVE**
AD / Identity Services 172.16.60.x	DR Site	AD replication to DR DC	Near real-time	TCP 636 / 389	**SCHEDULED**

4. Backup Strategy

4.1 Backup Policy — 3-2-1 Rule

The organisation follows the 3-2-1 backup rule:

- 3 copies of all critical data (production, local backup, DR site backup)
- 2 different storage media types (SAN/NAS array and backup-to-disk)
- 1 copy offsite at all times (DR Backup node at geographically separate DR site)

4.2 Backup Schedule

System	Backup Type	Schedule	Retention	Location	Verified
Core Banking DB 172.16.30.20	Transaction log backup	Every 15 minutes	7 days online 1 year archive	Backup 172.16.30.40 + DR Backup	**VERIFIED**
Core Banking DB 172.16.30.20	Full database backup	Daily 01:00	30 days online 7 years archive	Backup + DR Backup	**VERIFIED**
Transaction DB 172.16.30.21	Transaction log backup	Every 15 minutes	7 days online 1 year archive	Backup + DR Backup	**VERIFIED**
Transaction DB 172.16.30.21	Full database backup	Daily 01:30	30 days online 7 years archive	Backup + DR Backup	**VERIFIED**
Core Banking Server	VM snapshot	Daily 02:00	14 days	Backup + DR Backup	**VERIFIED**
Banking App 172.16.20.10	Application config + data	Daily 02:30	30 days	Backup 172.16.30.40	**VERIFIED**
Mobile Backend 172.16.20.11	Application config + data	Daily 02:30	30 days	Backup 172.16.30.40	**VERIFIED**
Active Directory 172.16.60.10	System state + AD backup	Daily 03:00	30 days	Backup + DR Backup	**VERIFIED**
Identity Services 172.16.60.x	Full configuration backup	Daily 03:00	30 days	Backup 172.16.30.40	**VERIFIED**
Wazuh SIEM 172.16.66.10	SIEM config + indices	Daily 04:00	90 days online 1 year archive	Backup + DR Backup	**VERIFIED**
Firewall configs (all 6 FWs)	Config export	Weekly Sunday	1 year	Backup 172.16.30.40	**VERIFIED**
Network device configs (all)	Config export via RANCID	Weekly Sunday	1 year	Backup 172.16.30.40	**VERIFIED**
PCI Payment systems 172.16.50.x	Full + incremental	Daily full Hourly incremental	1 year online 7 years archive	PCI-isolated backup + DR Backup	**VERIFIED**

> **Backup Integrity:** All backups are verified via monthly restore tests. Last full restore test completed February 2026 — all systems restored successfully within RTO targets.

5. Disaster Scenarios & Impact Assessment

The following scenarios are considered in this plan. Each is assigned a likelihood rating, impact rating, and recovery approach.

Scenario	Likelihood	Impact	Recovery Approach	Estimated Recovery Time
Primary DC complete outage (power, cooling, physical)	LOW	CRITICAL	Full failover to DR site. All Tier 1 systems recovered from DR Database and snapshots.	**3–4 hours to full Tier 1 restoration**
Core Banking DB corruption or ransomware	MEDIUM	CRITICAL	Isolate primary DB. Restore from last clean backup (max 15-min RPO). If unrecoverable, failover to DR Database.	**1–2 hours (restore) or 2 hours (DR failover)**
Data Centre network failure (DC Firewall failure)	LOW	HIGH	Failover DC Firewall using standby config. If unrecoverable, activate DR site for DB tier only.	**1–2 hours**
Storage array failure	LOW	HIGH	Fail over to Backup (172.16.30.40) which has bidirectional sync. Parallel activate DR Database.	**2–3 hours**
Ransomware — multi-system encryption	LOW	CRITICAL	Isolate all affected systems. Invoke DR. Restore from air-gapped DR Backup (last clean checkpoint).	**4–8 hours depending on blast radius**
Application tier compromise (Banking App / Mobile Backend)	MEDIUM	HIGH	Isolate compromised app servers. Restore from clean snapshots. DB remains in production.	**2–3 hours**
Partial DB failure — Transaction DB only	MEDIUM	HIGH	Restore Transaction DB from 15-min log backup. Core Banking DB remains live.	**1 hour**
ISP link failure (primary WAN)	MEDIUM	MEDIUM	Activate secondary ISP link via Border Router failover. No DC failover required.	**30 minutes**
Branch connectivity failure	HIGH	LOW	Branch VPN failover to secondary ISP. No DR invocation.	**1–2 hours**
SIEM / SOC outage	LOW	MEDIUM	Activate DR SIEM backup. No impact on banking operations. Reduced monitoring capability.	**8 hours**

6. Disaster Declaration Process

A disaster must be formally declared before any DR failover is initiated. The declaration process ensures that failover is not triggered prematurely and that the correct stakeholders are engaged.

6.1 Declaration Criteria

A disaster may be declared when any of the following thresholds are met:

- Primary Data Centre is confirmed unavailable and estimated recovery time exceeds 2 hours
- Core Banking DB or Transaction DB is confirmed corrupted, encrypted, or unrecoverable from local backup
- DC Firewall is unrecoverable and alternative traffic path is not available
- A security incident has resulted in confirmed compromise of the production database tier
- Regulatory or executive direction to activate the DR plan

6.2 Declaration Authority

Role	Name / Team	Authority
Primary Declarant	Business Continuity Manager	May declare disaster unilaterally during business hours
Secondary Declarant	CISO	May declare disaster at any time including out-of-hours
Technical Confirmation	DC Operations Lead	Must confirm technical assessment before declaration is finalised
Executive Notification	CTO / CEO	Must be notified within 30 minutes of declaration
Regulatory Notification	Compliance Officer	Must notify relevant regulators if outage exceeds regulatory threshold (typically 4 hours for banking)

7. DR Failover Procedure

This section defines the step-by-step failover procedure. The procedure is divided into phases. Each phase must be completed and verified before proceeding to the next.

> **IMPORTANT:** Do not proceed to the next phase until all steps in the current phase are marked complete and signed off by the Phase Lead. Premature progression risks data inconsistency between primary and DR systems.

Phase 1 — Assess & Declare (Target: 0–30 minutes)

Step	Action	Owner	Verification
1.1	Confirm primary DC is unavailable or unrecoverable within 2-hour window	DC Operations Lead	Document: incident ticket number, failure description, estimated recovery time
1.2	Notify CISO and Business Continuity Manager	DC Operations Lead	Confirmation receipt from both parties (call log or email)
1.3	Formally declare disaster — complete Disaster Declaration Form	BC Manager or CISO	Signed declaration form on file
1.4	Notify CTO and CEO within 30 minutes of declaration	BC Manager	Notification log entry
1.5	Notify Compliance Officer — assess regulatory notification requirement	Compliance Officer	Regulatory notification sent if threshold met
1.6	Activate DR Response Team — notify all Phase Leads	BC Manager	DR Response Team acknowledgement log
1.7	Open DR War Room (physical or video call bridge)	BC Manager	Bridge open. All Phase Leads dialled in.

Phase 2 — DR Site Readiness Check (Target: 30–60 minutes)

Step	Action	Owner	Verification
2.1	Confirm DR site network connectivity and power are operational	DC Operations	Ping test from DR site to OOB management VLAN confirmed
2.2	Confirm DR Replication node is healthy and replication lag is within RPO	DC Operations	Replication lag < 15 minutes for Tier 1 DBs. Document last replication timestamp.
2.3	Confirm DR Database has received latest transaction logs	DBA Lead	DR Database lag report — confirm within RPO window
2.4	Confirm DR Backup is consistent and last backup job completed successfully	DC Operations	Backup job log — last successful completion timestamp confirmed
2.5	Confirm DR site firewall rules are active and match primary DC configuration	Network Security	Firewall policy review — all required rules verified
2.6	Confirm DR site DNS entries are pre-staged and ready to activate	Network Engineer	DNS failover entries confirmed — A records ready to update

Step	Action	Owner	Verification
2.7	Assign DR node IP addresses if not yet provisioned	Network Engineer	IPs assigned and documented — unblock Observation DR-08

Phase 3 — Database Failover (Target: 60–120 minutes)

Step	Action	Owner	Verification
3.1	Stop replication to prevent split-brain — isolate DR Database from primary replication stream	DBA Lead	Replication stopped. DR Database in read-write standby mode.
3.2	Apply any outstanding transaction logs to DR Database (roll forward)	DBA Lead	DR Database is at latest consistent checkpoint. Document recovery point timestamp.
3.3	Promote DR Database to primary role — Core Banking DB	DBA Lead	DR Database accepting read-write connections. Connection string updated.
3.4	Promote DR Database to primary role — Transaction DB	DBA Lead	Transaction DB accepting read-write connections.
3.5	Verify data integrity — run automated integrity check scripts	DBA Lead	Integrity check passed. No corruption detected. Results logged.
3.6	Update application connection strings to point to DR Database	DC Operations	Banking App and Mobile Backend connection strings updated.
3.7	Confirm DB Firewall rules at DR site permit application → DB connections	Network Security	Test connection from DR Core Banking Server to DR Database — success

Phase 4 — Application & Identity Recovery (Target: 120–180 minutes)

Step	Action	Owner	Verification
4.1	Restore Active Directory at DR site from AD backup	AD Administrator	AD services online. User authentication functional.
4.2	Restore Identity Services (DNS 172.16.60.11, RADIUS 172.16.60.12, DHCP 172.16.60.13) at DR site	AD Administrator	DNS resolving. RADIUS responding. DHCP serving addresses.
4.3	Restore IAM Server and MFA Server from snapshots	DC Operations	IAM and MFA services online. Test authentication successful.
4.4	Restore Core Banking Server from latest clean snapshot	DC Operations	Core Banking Server online. Connects to DR Database successfully.
4.5	Restore Banking App (172.16.20.10) and Mobile Backend (172.16.20.11)	DC Operations	Application services online. Health check endpoints responding.
4.6	Restore Payment Gateway and PCI zone services from snapshots	DC Operations	Payment Gateway online. PCI firewall rules verified. Test transaction processed.

Step	Action	Owner	Verification
4.7	Activate SIEM monitoring at DR site — restore Wazuh from backup	SOC Lead	Wazuh SIEM online. Log ingestion confirmed from all DR systems.

Phase 5 — Cutover & Validation (Target: 180–240 minutes)

Step	Action	Owner	Verification
5.1	Update public DNS — point internet-facing services to DR site WAF / Reverse Proxy	Network Engineer	DNS propagation confirmed. TTL set to 60 seconds prior to failover.
5.2	Update internal DNS — all internal services point to DR site	Network Engineer	Internal DNS resolving to DR site IPs confirmed.
5.3	Execute end-to-end smoke test — banking transaction through full stack	QA / DC Operations	Test transaction completed successfully end-to-end at DR site.
5.4	Confirm all monitoring dashboards are active — SOC Dashboard (172.16.66.30)	SOC Lead	SOC Dashboard showing all DR systems. Alerts configured.
5.5	Declare DR site operational — notify all stakeholders	BC Manager	Stakeholder notifications sent. RTO achieved — document completion time.
5.6	Begin post-incident log collection for root cause analysis	SOC Lead	Evidence collection underway. Primary DC logs preserved.

8. Failback to Primary Data Centre

Failback to the primary Data Centre is initiated only after the root cause of the original disaster has been fully resolved and the primary DC has been verified as stable and secure. Failback is never rushed — operating at the DR site indefinitely is preferred over a premature failback that risks a second outage.

8.1 Failback Criteria

- Primary DC infrastructure is fully restored and verified stable for minimum 24 hours
- Root cause of the original incident is identified and confirmed remediated
- Security team has confirmed primary DC is free from any compromise or residual threat
- BC Manager and CISO have jointly approved the failback schedule
- Maintenance window has been agreed with the business — failback to occur outside peak hours

8.2 Failback Steps

Step	Action	Owner	Verification
FB-1	Rebuild and harden primary DC environment — apply all patches, verify firewall configs	DC Operations + Security	Primary DC security posture verified. Hardening checklist signed off.
FB-2	Begin reverse replication — sync data from DR Database back to primary DC databases	DBA Lead	Reverse replication active. Primary DB catching up with DR DB.
FB-3	Freeze writes on DR Database — ensure primary DB is fully synchronised	DBA Lead	Primary DB transaction count matches DR DB. Zero lag confirmed.
FB-4	Promote primary databases back to active primary role	DBA Lead	Primary Core Banking DB and Transaction DB accepting connections.
FB-5	Restore application services on primary DC — Banking App, Mobile Backend, IAM, MFA	DC Operations	Application health checks passing on primary DC.
FB-6	Update DNS to point back to primary DC	Network Engineer	DNS updated. Propagation confirmed. Traffic flowing to primary DC.
FB-7	Validate full end-to-end transaction on primary DC	QA / DC Operations	Test transaction successful on primary DC.
FB-8	Decommission DR site active services — return to warm standby	DC Operations	DR site in warm standby. Replication from primary to DR restarted.
FB-9	Conduct post-incident review — document lessons learned	BC Manager	Post-incident report issued within 5 business days of failback.

9. DR Testing Schedule

Regular testing is mandatory to validate that RTO and RPO targets are achievable and that all procedures remain current. Testing is categorised into three types.

Test Type	Description	Frequency	Next Date	Status
Backup Restore Test	Restore individual databases and servers from backup to isolated environment. Verify data integrity and restoration time.	Monthly	**April 2026**	**SCHEDULED**
Replication Validation	Verify replication lag is within RPO targets. Confirm DR Database consistency against primary.	Monthly	**April 2026**	**SCHEDULED**
Tabletop Exercise	Walkthrough of failover procedure with all Phase Leads. Identify process gaps without live system changes.	Quarterly	**June 2026**	**SCHEDULED**
Partial Failover Test	Fail over a single non-critical system (e.g. SIEM) to DR site. Validate DR infrastructure without impacting production.	Bi-annually	**Q2 2026**	**SCHEDULED**
Full DR Failover Test	Complete failover of all Tier 1 and Tier 2 systems to DR site. Validate full RTO and RPO. Includes failback.	Annually	**Q3 2026**	**SCHEDULED**
PCI DR Test	DR test specifically covering Payment Processing zone. Required annually by PCI-DSS v4.0.	Annually	**Q3 2026**	**SCHEDULED**

> **First Full DR Test:** The first full DR failover test is scheduled for Q3 2026 following completion of DR node IP provisioning (Observation DR-08). The Business Continuity Manager is responsible for scheduling this test and ensuring all Phase Leads are available.

10. Roles & Responsibilities

Role	Name / Team	Responsibilities
Business Continuity Manager	BC Team	Disaster declaration authority. DR plan owner. Coordinates War Room. Stakeholder communications. Ensures testing schedule is met.
CISO	Security Team	Joint declaration authority. Approves failback. Security sign-off on primary DC before failback. Regulatory notification oversight.
DC Operations Lead	DC Operations	Technical assessment of primary DC status. Phase 2 and 4 lead. DR site infrastructure readiness.
DBA Lead	Database Team	Phase 3 lead. Database failover, promotion, and integrity verification. Reverse replication for failback.
Network Security Engineer	Network Security	Firewall rule verification at DR site. DNS cutover. OOB management access. VPN tunnel configuration.
AD Administrator	Identity Team	Active Directory restoration at DR site. Identity Services recovery. LDAPS, RADIUS, DHCP.
SOC Lead	SOC Team	SIEM restoration at DR site. Monitoring activation. Evidence collection for post-incident review.
QA / Test Lead	DC Operations / QA	End-to-end smoke testing in Phases 4 and 5. Transaction validation. Failback validation.
Compliance Officer	Legal / Compliance	Regulatory notification. PCI-DSS incident reporting. Banking regulator communication.
CTO / CEO	Executive	Receives notification within 30 minutes of declaration. Strategic decisions on extended DR operation.

11. Emergency Contact List

The following contacts must be reachable within 30 minutes of a disaster declaration. Contact details are maintained in the secure configuration management system and updated quarterly.

Role	Primary Contact	Secondary Contact	Contact Method
Business Continuity Manager	[NAME]	[DEPUTY NAME]	Mobile (24x7) + Email + War Room bridge
CISO	[NAME]	[DEPUTY NAME]	Mobile (24x7) + Email
DC Operations Lead	[NAME]	[DEPUTY NAME]	Mobile (24x7) + Ops pager
DBA Lead	[NAME]	[DEPUTY NAME]	Mobile (24x7) + On-call rotation
Network Security Engineer	[NAME]	[DEPUTY NAME]	Mobile (24x7) + On-call rotation
AD Administrator	[NAME]	[DEPUTY NAME]	Mobile (24x7) + On-call rotation
SOC Lead	[NAME]	[DEPUTY NAME]	SOC hotline (24x7) + Mobile
Compliance Officer	[NAME]	[DEPUTY NAME]	Mobile (business hours) + Emergency mobile (out-of-hours)
CTO	[NAME]	[DEPUTY NAME]	Mobile (24x7)
DR Site Facility Manager	[NAME]	[DEPUTY NAME]	Mobile (24x7) + Facility hotline
ISP Primary Contact	[ISP NAME]	[NOC NUMBER]	ISP NOC hotline (24x7)
Cloud / DR Site Vendor	[VENDOR NAME]	[SLA CONTACT]	Vendor support line + Escalation manager

> **Security Note:** Do not store actual contact phone numbers or personal details in this document. Maintain the live contact list in the secure configuration management system (password-protected, access-controlled). This document holds role placeholders only.

12. Open Items & Dependencies

The following items must be resolved before the first full DR failover test can be executed.

ID	Item	Action Required	Owner	Target
DR-08	DR node IP addresses not yet assigned — DR Replication node, DR Database, and DR Backup have no IPs. Cannot be added to SIEM scope or firewall rules until provisioned.	Assign IP addresses to all three DR nodes. Define DR subnet. Add DR nodes to firewall rules and SIEM monitoring scope.	DC Operations	**Q2 2026**
DR-06	Wazuh agents not yet deployed on DR nodes — SIEM coverage at DR site incomplete pending IP provisioning.	Deploy Wazuh agents on all DR nodes once IPs are assigned. Add to Log Collector scope.	SOC Team	**Q3 2026**
DR-04	DR site security hardening not yet validated — security controls at DR site not confirmed to match primary DC posture.	Run hardening checklist (SEC-DOC-008) against all DR nodes once provisioned. Document deviations.	DC Operations + Security	**Q3 2026**
DR-05	DR site user provisioning not synchronised with primary AD — users may not be able to log in at DR site immediately after failover.	Configure AD replication from primary to DR site DC. Verify user login capability at DR site in tabletop exercise.	AD Administrator	**Q3 2026**

Appendix A: RTO / RPO Summary Card

Quick reference card for use during an incident. Post in War Room and distribute to all Phase Leads.

RECOVERY TIME OBJECTIVE (RTO)

Tier 1 (Core Banking DB, Transaction DB, Payment GW)

2 hours

Tier 2 (Apps, Identity, Mobile Backend)

4 hours

Overall DR target (formal declaration to Tier 2 live)

4 hours

RECOVERY POINT OBJECTIVE (RPO)

Tier 1 databases (transaction log backup every 15 min)

15 minutes

Tier 2 systems (daily backup + snapshot)

1 hour

Overall maximum acceptable data loss

1 hour

Appendix B: Revision History

Version	Date	Author	Description
1.0	March 2026	Business Continuity Manager	Initial release. DR replication confirmed (Architecture Issue #6 resolved). RTO 4hr / RPO 1hr defined. Failover and failback procedures documented. Testing schedule defined. DR-08 (IP provisioning), DR-04, DR-05, DR-06 noted as open items for Q2/Q3 2026.

Appendix C: Related Documents

Ref	Document Title	Status
SEC-DOC-001	Security Architecture Overview	**Published v2.0**
SEC-DOC-002	Network Segmentation & VLAN Design	Pending
SEC-DOC-003	Firewall Policy & Rules	**Published v1.0**
SEC-DOC-004	Log Collection & SIEM Architecture	Pending
SEC-DOC-005	Identity & Access Management (IAM)	**Published v1.0**
SEC-DOC-006	Data Flow Diagram & Traffic Matrix	Pending
SEC-DOC-007	Disaster Recovery & Backup Plan (this document)	**Published v1.0**
SEC-DOC-008	Security Controls & Hardening Checklist	**Published v2.0**